



Hydro-Check
SYSTEMS, INC

Water Quality Instrumentation
Conductivity • %Rejection • TDS • Resistivity

5931 Sea Lion Place Ste 100
Carlsbad, CA 92010
Tel: 760-930-1924
Fax: 760-930-1934
www.hydrocheck.com

Re: Test Points for CM-1K Verification (01/01/17)

This notice is to provide test points to verify the reliability of the CM-1K, calibration Module. All readings below were taken with a multi-meter, in current calibration.

1. Turn on multi-meter and set to Ohms (Ω)
2. Touch one probe end to pin 7 and the other to pin 8. You should get a stable reading of 1.066k, +/- .1%
3. Touch one probe end to pin 10 and the other to pin 11. You should get a stable reading of 13.56k, +/- .1%
4. Verification Complete.

Scott Brown
Operations Manager